

# A1 Supermarket - Burgersfort

Wall Consultant: TMV Consulting

Contractor: Rabe Construction

Client: A1 Supermarket

Block supplier: Aveng Manufacturing Infraset

Duration: 8 weeks

Wall face area: 470 m<sup>2</sup>

The property area was very restricted and EIS had to make the most of the available space. An 8m high wall with an 85° face angle was the solution. The embankment was cut back 5m to create space for the geosynthetic reinforcement required. Wickdrains, together with a collector drain was installed against the back face with outlets through the wall face.

